



FOR CONSTRUCTION
FULLY SPRINKLERED

4. CONTRACTOR SHALL BE RESPONSIBLE FOR SECURING AND UTILIZING AN UNDERGROUND UTILITY LOCATING SERVICE TO MARK ON THE GROUND SURFACE THE LOCATION OF UNDERGROUND UTILITIES ON SITE THAT ARE NOT COVERED IN THE PA ONE CALL NOTIFICATION.

Demolition Key Notes

◆ DE-ENERGIZE AND REMOVE ALL TELECOMMUNICATION CABLEING FED FROM BUILDING #5. DE-ENERGIZE AND PULL BACK FIRE ALARM OPTICAL FIBER CABLE. RE-ESTABLISH CAMPUS FIRE ALARM LOOP IN BUILDING #5. SCHEDULE ANY OUTAGE WITH CONTRACTING OFFICERS' TECHNICAL REPRESENTATIVE.

◆ DE-ENERGIZE AND REMOVE ALL CABLEING, CUT AND CAP UNDERGROUND CONDUIT FOR FUTURE EXTENSION.

◆ EXISTING GUARD SHACK TO BE DE-ENERGIZE, DISCONNECTED AND REMOVED AFTER NEW SHACK IS OPERATIONAL. MAINTAIN TELECOMMUNICATION SERVICE TO SHACK UNTIL NEW SHACK IS OPERATIONAL.