

**SECTION 32 90 00**  
**PLANTING****PART 1 - GENERAL****1.1 DESCRIPTION**

- A. This work consists of furnishing and installing all planting materials and benches required for landscaping hereinafter specified in locations as shown.

**1.2 EQUIPMENT**

- A. Maintain all equipment, tools and machinery while on the project in sufficient quantities and capacity for proper execution of the work.

**1.3 RELATED WORK**

- A. Section 31 20 00, EARTH MOVING, Stripping Topsoil and Stock Piling.  
B. Section 01 45 29, TESTING LABORATORY SERVICES, Topsoil Testing.  
C. Section 31 20 00, EARTH MOVING, Topsoil Materials.  
D. Section 01 57 19, TEMPORARY ENVIRONMENTAL CONTROLS.

**1.4 SUBMITTALS**

- A. Samples: Submit the following samples for approval before work is started:

Inert Mulch	2.3 kg (5 pounds) of each type to be used.
Organic Mulch	2.3 kg (5 pounds) of each type to be used.
Pre-Emergent Herbicide	2.3 kg (5 pounds) of each type to be used.

- B. Certificates of Conformance or Compliance: Before delivery, notarized certificates attesting that the following materials meet the requirements specified shall be submitted to the Resident Engineer for approval:

1. Plant Materials (Department of Agriculture certification by State Nursery Inspector declaring material to be free from insects and disease).
2. Fertilizers.
3. Lime
4. Peat
5. Seed
6. Membranes
7. Asphalt Adhesive

- C. Manufacturer's Literature and Data:

1. Metal edging
2. Antidesiccant

D. Soil laboratory testing results and any soil amendment recommendations from the Contractor.

E. Benches:

1. Product Data: Submit manufacturer's product data, storage and handling requirements and recommendations, installation methods and available colors, styles, patterns and textures.
2. Shop Drawings: Submit manufacturer's shop drawings, including plans and elevations, indicating overall dimensions.
3. Samples: Submit manufacturer's samples of materials, finishes, and colors.
4. Warranty: Manufacturer's standard warranty.

#### **1.5 DELIVERY AND STORAGE**

A. Delivery:

1. Notify the Resident Engineer of the delivery schedule in advance so the plant material may be inspected upon arrival at the job site. Remove unacceptable plant material from the job site immediately.
2. Protect plants during delivery to prevent damage to root balls or desiccation of leaves. Protect trees during transport by tying in the branches and covering all exposed branches.
3. The use of equipment such as "tree spades" is permitted provided the plant balls are sized in accordance with ANSI Z60.1 and tops are protected from damage.
4. Deliver fertilizer and lime to the site in the original, unopened containers bearing the manufacturer's warranted chemical analysis, name, trade name or trademark, and in conformance to state and federal law. In lieu of containers, fertilizer and lime may be furnished in bulk and a certificate indicating the above information shall accompany each delivery.
5. During delivery: Protect sod, from drying out and seed from contamination.

B. Storage:

1. Keep seed, lime, and fertilizer in dry storage away from contaminants.
2. Store plants not installed on the day of arrival at the site as follows:
  - a. Shade and protect plants from the wind when stored outside.
  - b. Heel in bare root plants.

- c. Protect plants stored on the project from drying out at all times by covering the balls or roots with moist sawdust, wood chips, shredded bark, peat moss, or other similar mulching material.
- d. Keep plants, including those in containers, in a moist condition until planted, by watering with fine mist spray.

#### **1.6 PLANTING AND TURF INSTALLATION SEASONS AND CONDITIONS**

- A. Perform operations within the following dates: From March 1 to June 1 for spring and from August 15 to October 15 for fall.
- B. No work shall be done when the ground is frozen, snow covered, too wet or in an otherwise unsuitable condition for planting. Special conditions may exist that warrants a variance in the specified planting dates or conditions. Submit a written request to the Resident Engineer stating the special conditions and proposal variance.

#### **1.7 PLANT AND TURF ESTABLISHMENT PERIOD**

- A. The Establishment Period for plants and turf shall begin immediately after installation, with the approval of the Resident Engineer, and continue until the date that the Government accepts the project or phase for beneficial use and occupancy. During the Plant and Turf Establishment Period the Contractor shall:
  - 1. Water all plants and turf to maintain an adequate supply of moisture within the root zone. An adequate supply of moisture is the equivalent of 25 mm (1 inch) of absorbed water per week either through natural rainfall or augmented by periodic watering. Apply water at a moderate rate so as not to displace the mulch or flood the plants and turf.
  - 2. Prune plants and replace mulch as required.
  - 3. Replace and restore stakes, guy wires, and eroded plant saucers as required.
  - 4. In plant beds and saucers, remove grass, weeds, and other undesired vegetation, including the root growth, before they reach a height of 75 mm (3 inches).
  - 5. Spray with approved insecticides and fungicides to control pests and ensure plant survival in a healthy growing condition, as directed by the Resident Engineer.
  - 6. Provide the following turf establishment:
    - a. Eradicate all weeds. Water, fertilize, overseed, and perform any other operation necessary to promote the growth of grass.
    - b. Replant areas void of turf 0.1 m<sup>2</sup> (one square foot) and larger in area.

- c. Mow the new lawn at least three times prior to the final inspection. Begin mowing when grass is 100 mm (4 inches) high. Mow to a 65 mm (2-1/2 inch) height.
- 7. Remove plants that die during this period and replace each plant with one of the same size and species.

#### **1.8 PLANT AND TURF WARRANTY**

- A. All work shall be in accordance with the terms of the Paragraph, "Warranty" of FAR clause 52.246-21, including the following supplements:
  - 1. A One Year Plant and Turf Warranty will begin on the date that the Government accepts the project or phase for beneficial use and occupancy. The Contractor shall have completed, located, and installed all plants and turf according to the plans and specifications. All plants and turf are expected to be living and in a healthy condition at the time of final inspection.
  - 2. The Contractor will replace any dead plant material and any areas void of turf immediately. A one year warranty for the plants and turf that was replaced, will begin on the day the work is completed.
  - 3. Replacement of relocated plants, that the Contractor did not supply, is not required unless they die from improper handling and care during transplanting. Loss through Contractor negligence requires replacement in kind and size.
  - 4. The Government will reinspect all plants and turf at the end of the One Year Warranty. The Contractor will replace any dead, missing, or defective plant material and turf immediately. The Warranty will end on the date of this inspection provided the Contractor has complied with the work required by this specification. The Contractor shall also comply with the following requirements:
    - a. Replace dead, missing or defective plant material prior to final inspection.
    - b. Mulch and weed plant beds and saucers. Just prior to this inspection, treat these areas to a second application of approved pre-emergent herbicide.
    - c. From plants having been installed for one year, remove stakes, guy wires and any required tree wrappings.
    - d. Complete remedial measures directed by the Resident Engineer to ensure plant and turf survival.
    - e. Repair damage caused while making plant or turf replacements.
- B. Benches: Products will be free from defects in material and/or workmanship for a period of three years from the date of substantial

completion. The warranty does not apply to damage resulting from accident, alteration, misuse, tampering, negligence, or abuse.

### 1.9 APPLICABLE PUBLICATIONS

- A. The publications listed below, form a part of this specification to the extent referenced. The publications are referenced in the text by basic designation only.
- B. American National Standards Institute (ANSI) Publications:
  - ANSI Z60.1-04.....Nursery Stock
  - ANSI Z133.1-06.....Tree Care Operations-Pruning, Trimming, Repairing, Maintaining, and Removing Trees and Cutting Brush- Safety Requirements
- C. Hortus Third, A Concise Dictionary of Plants Cultivated in the U.S. and Canada.
- D. American Society for Testing and Materials (ASTM) Publications:
  - C136-06.....Sieve Analysis of Fine and Coarse Aggregates
  - D977-05.....Emulsified Asphalt (AASHTO M140)
  - D2103-05.....Polyethylene Film and Sheeting
- E. U. S. Department of Agriculture Federal Seed Act.
  - 1998.....Rules and Regulations
- F. American Wood Protection Association (AWPA):
  - C2-02.....Lumber, Timbers, Bridge Ties and Mine Ties, Pressure Treatment

## PART 2 - PRODUCTS

### 2.1 GENERAL

- A. All plant and turf material will conform to the varieties specified or shown in the plant list and be true to botanical name as listed in Hortus Third.

### 2.2 PLANTS

- A. Plants shall be in accordance with ANSI Z60.1, except as otherwise stated in the specifications or shown on the plans. Where the drawings or specifications are in conflict with ANSI Z60.1, the drawings and specification shall prevail.
- B. Provide well-branched and formed planting stock, sound, vigorous, and free from disease, sunscald, windburn, abrasion, harmful insects or insect eggs with healthy, normal, and unbroken root systems. Provide trees, deciduous and evergreen, that are single trunked with a single leader, unless otherwise indicated, display no weak crotches. Provide symmetrically developed deciduous trees and shrubs of uniform habit of growth, with straight boles or stems and free from objectionable

disfigurements, and evergreen trees and shrubs with well developed symmetrical tops with typical spread of branches for each particular species or variety. Provide ground cover and vine plants with the number and length of runners for the size specified, and the proper age for the grade of plants specified. Provide vines and ground cover plants well established in removable containers, integral containers, or formed homogeneous soil sections. Plants shall have been grown under climatic conditions similar to those in the locality of the project. Spray all plants budding into leaf or having soft growth with an anti-desiccant at the nursery before digging.

- C. The minimum acceptable sizes of all plants, measured before pruning with branches in normal position, shall conform to the measurements designated. Plants larger in size than specified may be used with the approval of the Resident Engineer, with no change in the contract price. When larger plants are used, increase the ball of earth or spread of roots in accordance with ANSI Z60.1.
- D. Provide nursery grown plant material conforming to the requirements and recommendations of ANSI Z60.1. Dig and prepare plants for shipment in a manner that will not cause damage to branches, shape, and future development after planting.
- E. Balled and burlapped (B&B) plant ball sizes and ratios will conform to ANSI Z60.1, consisting of firm, natural balls of soil wrapped firmly with burlap or strong cloth and tied.
- F. Bare-root (BR) plants shall have the root system substantially intact, but with the earth carefully removed. Cover roots with a thick coating of mud by "puddling" after the plants are dug.
- G. Container grown plants shall have sufficient root growth to hold the earth intact when removed from containers, but shall not be root bound.
- H. Make substitutions only when a plant (or its alternates as specified) is not obtainable and the Resident Engineer authorizes a change order providing for use of the nearest equivalent obtainable size or variety of plant having the same essential characteristics with an equitable adjustment of the contract price.
- I. When existing plants are to be relocated, ball sizes shall conform to requirements for collected plants in ANSI Z60.1, and plants shall be dug, handled, and replanted in accordance with applicable sections of these specifications.

### **2.3 LABELS**

- A. Each plant, or group and bundles or containers of the same species, variety, and size of plant, shall be legibly tagged with a durable,

waterproof and weather-resistant label indicating the correct plant name and size specified in the plant list. Labels shall be securely attached and not be removed.

#### **2.4 TOPSOIL**

- A. Topsoil shall be a well-graded soil of good uniform quality. It shall be a natural, friable soil representative of productive soils in the vicinity. Topsoil shall be free of admixture of subsoil, foreign matter, objects larger than 25 mm (one inch) in any dimension, toxic substances, weeds and any material or substances that may be harmful to plant growth and shall have a pH value of not less than 5.0 nor more than 7.5.
- B. Sufficient topsoil is not available on the site to meet the depth as specified herein. The Contractor shall furnish additional topsoil. At least 10 days prior to topsoil delivery, notify the Resident Engineer of the source(s) from which topsoil is to be furnished. Obtain topsoil from well drained areas. Topsoil shall meet the general requirements as stated above and comply with the requirements specified in Section 01 45 29, TESTING LABORATORY SERVICES. Amend topsoil not meeting the pH range specified by the addition of pH adjusters.

#### **2.5 LIME**

- A. Lime shall be agricultural limestone containing not less than 90 percent calcium and magnesium carbonates. Lime must be ground to such a fineness that not less than 90% must pass No. 8 mesh and not less than 25% must pass No. 100 mesh. Moisture is not to exceed 10%.

#### **2.6 SOIL CONDITIONERS**

- A. Peat shall be a natural product of sphagnum moss peat derived from a fresh-water site conforming to Fed. Spec. Q-P-166, except as otherwise specified. Peat shall be shredded and granulated to pass through a 13 mm (1/2inch) mesh screen and conditioned in storage piles for at least six months after excavation.
- B. Organic Matter shall be commercially prepared compost, composted sufficiently to be free of all woody fibers, seeds, and leaf structures, and free of toxic and nonorganic matter.
- C. Fertilizer: Agricultural fertilizer of a formula indicated by the soil test. Fertilizers shall be organic, slow-release compositions whenever applicable

#### **2.7 PLANTING SOIL MIXTURE**

- A. The planting soil mixture shall be composed of 5 parts topsoil, and 1/2 part peat moss and 1/2 part organic matter.

**2.8 PLANT FERTILIZER**

- A. Provide plant fertilizer that is commercial grade and uniform in composition and conforms to applicable state and federal regulations.
- B. For new plant material, provide packet, table, or pellet forms of slow release fertilizers, bearing the manufacturer's warranted statement of analysis. Slow release fertilizers shall contain a minimum percentage by weight of 10 percent nitrogen (of which 50 percent will be organic), 10 percent available phosphoric acid, and 10 percent potash.

**2.9 TURF FERTILIZER**

- A. Provide turf fertilizer that is commercial grade, free flowing, uniform in composition, and conforms to applicable state and federal regulations. Granular fertilizer shall bear the manufacturer's warranted statement of analysis. Granular fertilizer shall contain a minimum percentage by weight of 20 percent nitrogen (of which 50 percent shall be organic), 10 percent available phosphoric acid, and 10 percent potash. Liquid starter fertilizer for use in the hydro seed slurry will be commercial type with 50 percent of the nitrogen in slow release form.

**2.10 MEMBRANES**

- A. Landscape Fabric shall be a spunbonded polyester fabric weighing 18 grams per square meter ( $\frac{3}{4}$  oz per sq. yd) and with a 9,000 liter per minute flow rate per sq. meter (225 gal. per minute flow rate per sq. ft.).

**2.11 MULCH**

- A. Mulch shall be free from deleterious materials and shall be stored as to prevent inclusion of foreign material.
- B. Inert mulch materials shall be riverbank stone and shall range in size from 25 mm (one inch) to 65 mm (2-1/2 inches) in accordance with ASTM C 136.
- C. Organic mulch materials shall be straw shredded hardwood bark
  - 1. Straw for lawn seed bed mulch shall be stalks from oats, wheat, rye, barley, or rice that are free from noxious weeds, mold or other objectionable material. Straw shall be in an air-dry condition and suitable for placing with blower equipment.  
or applied water to percolate to the underlaying soil.

**2.12 ASPHALT ADHESIVE**

- A. Asphalt adhesive for application with straw mulch shall be emulsified asphalt conforming to ASTM D977, Grade RS-1.

**2.13 TREE WRAP**

- A. Extruded, translucent, twin-walled polypropylene protection board sheets; 3 mm thick. 1800mm (6 ft) long tree shelters may be utilized for



short trunk trees 75 mm (3 in.) caliper or less. Submit manufacturer literature for approval. C. Breathable synthetic fabric tree wrap. White in color, delivered in 75 mm (3 in.) wide rolls. Specifically manufactured for tree wrapping. Tree wrap shall be "Breathable Fabric Tree Wrap" as manufactured by the Dewitt Company, Inc., Sikeston, MO, or approved equal. Submit manufacturer literature for approval.

- B. Tree wrap shall be secured to the trunk using bio-degradable tape suitable for nursery use and which is expected to degrade in sunlight in less than two years after installation

#### **2.14 STAKES AND GUYING WIRES**

- A. Provide stakes for tree support of rough sawn wood, free from knots, rot, cross grain, or other defects that would impair the strength. Stakes shall be a minimum of 50 mm by 50 mm (2 inches by 2 inches), or 65 mm (2-1/2 inches) in diameter, by 2400 mm (8 feet) long and pointed at one end.
- B. Guying wire shall be 2.7 mm (12 gage) annealed galvanized steel.
- C. Hose chafing guards shall be new or used 2-ply reinforced rubber of all the same color on the project.
- D. Flags to be fastened to guys shall be surveyor's plastic tape, yellow in color and 150 mm (6 inches) in length.
- E. Guying cable shall be a minimum of five strand twisted, 5 mm (3/16 inch) diameter steel cable.
- F. Turnbuckles shall be galvanized or cadmium plated and have a 75 mm (3 inch) minimum lengthwise opening fitted with screw eyes.
- G. Eye bolts shall be galvanized or cadmium plated having a 50 mm (one inch) diameter eye with a minimum screw length of 40 mm (1-1/2 inches).

#### **2.15 EDGING**

- A. Metal edging shall be galvanized steel or aluminum with slots provided for stakes and shall be 5 mm (3/16 inch) thick by zero inches) deep in standard lengths. Anchoring stakes shall be of similar material and 400 to 450 mm (16 to 18 inches) long and tapered.

#### **2.16 WATER**

- A. Water shall not contain elements toxic to plant life. It shall be obtained from Government at no cost to Contractor in accordance with Article 1.19 Availability and Use of Utility Services Section 01 00 00, GENERAL REQUIREMENTS.

#### **2.17 ANTIDESICCANT**

- A. Antidesiccant shall be an emulsion specifically manufactured for agricultural use that will provide a protective film over plant surfaces permeable enough to permit transpiration.

**2.18 SEED**

- A. Seed shall be state-certified seed of the latest season's crop and shall be delivered in original sealed packages bearing the producer's warranted analysis for percentages of mixtures, purity, germination, weed seed content, and inert material. Seed shall be labeled in conformance with U. S. Department of Agriculture rules and regulations under the Federal Seed Act and applicable state seed laws. Seed that has become wet, moldy, or otherwise damaged will not be acceptable. Onsite seed mixing shall be done only in the presence of the Resident Engineer. Seed mixtures shall be proportioned by weight as follows:

## NAME OF GRASS

(Botanical and Common)	<u>Percent by Weight</u>
Poa pratensis (Kentucky Bluegrass)	50
Festuca cubra (Red Fescue)	30
Lolium perenne (Turf-type Perennial Ryegrass)	20
<hr/>	
<u>Percent Germination</u>	<u>Maximum Percent Weed Seed</u>
80	0.20
85	0.15
90	0.15
<hr/>	

**2.19 BENCHES**

- A. Manufacturer: Landscape Forms, Inc., 431 Lawndale Avenue, Kalamazoo, Michigan 49048. Toll Free (800) 521-2546. Phone (269) 381-0396. Fax (269) 381-3455. Website [www.landscapeforms.com](http://www.landscapeforms.com). E-mail: [specify@landscapeforms.com](mailto:specify@landscapeforms.com); or equivalent.
- B. Type: Sit.
- C. Style:
1. Backed:
    - a. Depth: 24-3/4 inches.
    - b. Overall Height: 32-1/4 inches.
    - c. Length: 74 inches.
  2. Mounting: Surface mounted.
- D. Supports: End supports are type 319 ASTM B 26 aluminum sand casting.
- E. Frame: Seat rails are 1/5" outer diameter x 0.120" wall ASTM A 513 type 1 steel tubing with type 304 ASTM A 276 stainless steel threaded inserts welded inside each end. Seat panel connections are 0.250" x 0.75" x

0.80" type 304 ASTM A 276 stainless steel flat bar welded to rail.

Upper and lower back rails are 6061-T6 or 6005A-T5 ASTM B 211 aluminum extrusions. Upper rail is 1.375" diameter; lower rail is 0.875" diameter.

- F. Seat and Back Panels: Seat panel is 0.120" thick ASTM A 1011 hot rolled pickled and oiled commercial steel type B perforated and formed. Seat panel connections are 0.188" x 1" x 1.5" type 304 ASTM A 276 stainless steel flat bar welded to panel. Back and side panels are 0.125" thick 3003-H14 ASTM B 209 aluminum sheet perforated and formed. Back panel is welded to back rails; side panels are welded to end castings.
- G. Surface Mount Plates: 0.375" thick 6061-T6511 ASTM B 221 aluminum flat bar.
- H. Fasteners: All threaded fasteners are stainless steel or Magni 565 coated carbon steel. Seat dividers are attached with nylon shoulder and flat washers to protect the seat panel finish.
- I. Anchor Bolts: Manufacturer's recommended corrosion resistant.
- J. Finish on Metal: Landscape Forms, Inc. "Pangard II".
  - 1. Primer: Rust inhibitor.
  - 2. Topcoat: Thermosetting polyester powder coat. UV, chip, and flake resistant.

### **PART 3 - EXECUTION**

#### **3.1 LAYOUT**

- A. Stake plant material locations and bed outlines on project site for approval by the Resident Engineer before any plant pits or beds are dug. The Resident Engineer may approve adjustments to plant material locations to meet field conditions.

#### **3.2 EXCAVATION FOR PLANTING**

- A. Prior to excavating for plant pits and bed, verify the location of any underground utilities. Damage to utility lines will be repaired at the Contractor's expense. Where lawns have been established prior to planting operation, cover the surrounding turf before excavations are made in a manner that will protect turf areas. Barricade existing trees, shrubbery, and beds that are to be preserved in a manner that will effectively protect them during the project construction.
- B. Remove rocks and other underground obstructions to a depth necessary to permit proper planting according to plans and specifications. Where underground utilities, construction, or solid rock ledges are encountered, the Resident Engineer may select other locations for plant material.

- C. Dig plant pits by any approved method so that they have vertical sides and flat bottoms. When pits are dug with an auger and the sides of the pits become glazed, scarify the glazed surface. Size the plant pits as shown, otherwise, the minimum allowable dimensions of plant pits shall be regardless of width, 150 mm (6 inches) deeper for shrubs for trees - pits shall be the same depth as the depth of ball or root spread for trees and shrubs pit diameters shall be twice the ball or root spread.
- D. Where ground cover and planting beds occur in existing turf areas, remove turf to a depth that will ensure the removal of the entire root system, with additional bed preparation as specified in the next paragraph.
- E. Where existing soil is to be used in place, till new ground cover and plant beds to a depth of 100 mm (4 inches). Spread peat uniformly over the bed to depth of 50 mm (2 inches) and thoroughly incorporate it into the existing soil to a depth of 100 mm (4 inches) using a roto-tiller or similar type of equipment to obtain a uniform and well pulverized soil mix. Where existing soil is compacted (former roadways, parking lots, etc.) till the soil down to a depth necessary to support the growth of new planting. During tillage operations, remove all sticks, stones, roots, and other objectionable materials. Bring plant beds to a smooth and even surface conforming to established grades.
- F. In areas of new grading where existing soil is being replaced for the construction of new ground cover and plant beds, remove 100 mm (4 inches) of existing soil and replace with topsoil. Plant beds shall be brought to a smooth and even surface conforming to established grades. Till 50 mm (2 inches) of peat into the topsoil as specified.
- G. Using topsoil, form earth saucers or water basins for watering around plants. Basins to be 2" high for shrubs and 4" high for trees.

### 3.3 SETTING PLANTS

- A. Handle balled and burlapped and container-grown plants only by the ball or container. Remove container-grown plants in such a way to prevent damage to plants or root system. Set plants plumb and hold in position until sufficient soil has been firmly placed around the roots or ball. Set plants so that the root crown is 1" higher than the surrounding grade. Plant ground cover plants after the mulch is in place. Avoid contaminating the mulch with the planting soil. Add slow release packet, tablet or pellet fertilizer as each plant is installed as per manufacturer's recommendation for method of installation and quantity.
- B. Backfill balled and burlapped and container-grown plants with planting soil mixture as specified to approximately half the depth of the ball

and then tamp and water. For balled and burlapped plants, carefully remove excess burlap and tying materials and fold back. Where plastic wrap or treated burlap is used in lieu of burlap, completely remove these materials before backfilling. Tamp and water remainder of backfill Planting Soil Mixture; then form earth saucers or water basins around isolated plants with topsoil.

- C. Plant bare-root stock arranging the roots in a natural position. Remove damaged roots with a clean cut. Carefully work Planting Soil Mixture in among the roots. Tamp and water the remainder of Planting Soil Mixture; then form earth saucers or water basins around isolated plants with topsoil.

### **3.4 TRUNK WRAPPING**

- A. Wrap the trunks of deciduous trees immediately after planting. Wrap the trunks of deciduous trees, 40 mm (1-1/2 inches) or greater in caliber with the specified material beginning at the base and extending to the first branches. Remove wrapping after one year. .

### **3.5 STAKING AND GUYING**

- A. Stake and guy plants as shown on the drawings and as specified.
- B. Drive stakes vertically into the ground to a depth of 800 to 900 mm (2-1/2 to 3 feet) in such a manner as not to injure the ball or roots, unless otherwise shown on the drawings.
- C. Fasten flags securely on each guy wire.
- D. Remove stakes and guy wires after one year.

### **3.6 EDGING PLANT BEDS**

- A. Uniformly edge beds using a sharp tool to provide a clear cut division line between the planted area and the adjacent lawn.
- B. Install metal edging materials in accordance with manufacturer's recommendations and as shown on the plans.

### **3.7 MULCHING PLANTS**

- A. Mulch within 48 hours after planting and applying a pre-emergent herbicide. Do not mulch in ground cover areas that shall have organic material placed before planting.
- B. Placing Inert Material: Place Landscape fabric with edges lapped 150 mm to 300 mm (6 inches to 12 inches) to receive inert mulch material. Spread inert mulch to a uniform thickness of 4 inches over the membrane or as shown.
- C. Placing Organic Material: Spread a mulch of shredded hardwood bark to a uniform minimum thickness of 100 mm (4 inches).
- D. Keep mulch out of the crowns of shrubs and off buildings, sidewalks, light standards, and other structures.

**3.8 PRUNING**

- A. Prune new plant material and indicated existing plant material in the following manner: Remove dead, broken and crossing branches. Prune deciduous trees and shrubs to reduce total amount of anticipated foliage by 1/4 to 1/3 while retaining typical growth habit of individual plants with as much height and spread as is practicable. Make cuts with sharp instruments as close as possible to the branch collar. Do not make flush cuts. Do not make "Headback" cuts at right angles to line of growth. Do not pole trees or remove the leader. Remove trimmings from the site. Paint cuts 13 mm (1/2 inch) in diameter and larger with the specified tree wound dressing.

**3.9 TILLAGE FOR TURF AND PLANTING AREAS**

- A. Thoroughly till the soil to a depth of at least 200 mm (8 inches) by scarifying, disking, harrowing, or other approved methods. This is particularly important in areas where heavy equipment has been used, and especially under wet soil conditions. Remove all debris and stones larger than 25 mm (one inch) remaining on the surface after tillage in preparation for finish grading. To minimize erosion, do not till areas of 3:1 slope ratio or greater. Scarify these areas to a 50 mm (one inch) depth and remove debris and stones.

**3.10 FINISH GRADING**

- A. After tilling the soil for bonding of topsoil with the subsoil, spread the topsoil evenly to a minimum depth of 150 mm (6 inches). Incorporate topsoil at least 50 to 75 mm (2 to 3 inches) into the subsoil to avoid soil layering. Do not spread topsoil when frozen or excessively wet or dry. Correct irregularities in finished surfaces to eliminate depressions. Protect finished topsoil areas from damage by vehicular or pedestrian traffic. Complete lawn work only after areas are brought to finished grade.

**3.11 APPLICATION OF FERTILIZER AND LIME FOR TURF AREAS**

- A. Apply nitrogen turf fertilizer at the rate of 2.2 kg/100 m<sup>2</sup> (1 pound per 1,000 square feet). In addition, adjust soil acidity and add soil conditioners as required herein for suitable topsoil under PART 2, Paragraph, TOPSOIL.
- B. Spread lime at the rate of 88 kg/100 m<sup>2</sup> (40 pounds per 1,000 square feet).
- C. Incorporate fertilizers and lime into the soil to a depth of at least 50 mm (2 inches) as part of the finish grading operation. Immediately restore the soil to an even condition before any turf work.

**3.12 MECHANICAL SEEDING**

- A. Broadcast seed by approved sowing equipment at the rate of 6.6 kg/100 m<sup>2</sup> (3 pounds per 1,000 square feet). Sow one half of the seed in one direction, and the remainder sown at right angles to the first sowing. Cover seed to an average depth of 6 mm (1/4 inch) by means of spike-tooth harrow, cultipacker, or other approved device.
- B. Immediately after seeding, firm up the entire area with a roller not exceeding 225 kg/m (150 pounds per foot) of roller width. Where seeding is performed with a cultipacker-type seeder or where seed is applied in combination with hydro-mulching, no rolling is required.
- C. Immediately after preparing the seeded area, evenly spread an organic mulch of straw by hand or by approved mechanical blowers at the rate of 0.5 kg/m<sup>2</sup> (2 tons per acre). Application shall allow some sunlight to penetrate and air to circulate but also reduce soil and seed erosion and conserve soil moisture. Anchor mulch by either a mulch tiller, asphalt emulsion, twine, or netting. When asphalt emulsion is used, apply either simultaneously or in a separate application. Take precautionary measures to prevent asphalt materials from marking or defacing structures, pavements, utilities, or plantings.

**3.13 WATERING**

- A. Apply water to the turf areas immediately following installation at a rate sufficient to ensure thorough wetting of the soil to a depth of at least 100 mm (4 inches). Supervise watering operation to prevent run-off. Supply all pumps, hoses, pipelines, and sprinkling equipment. Repair all areas damaged by water operations.

**3.14 PROTECTION OF TURF AREAS**

- A. Immediately after installation of the turf areas, protect against traffic or other use by erecting barricades, as required, and placing approved signs at appropriate intervals until final acceptance.

**3.15 RESTORATION AND CLEAN-UP**

- A. Where existing or new turf areas have been damaged or scarred during planting and construction operations, restore disturbed area to their original condition. Keep at least one paved pedestrian access route and one paved vehicular access route to each building clean at all times. In areas where planting and turf work have been completed, clear the area of all debris, spoil piles, and containers. Clear all other paved areas when work in adjacent areas is completed. Remove all debris, rubbish and excess material from the station.

**3.16 ENVIRONMENTAL PROTECTION**

- A. All work and Contractor operations shall comply with the requirements of Section 01 57 19, TEMPORARY ENVIRONMENTAL CONTROLS.

**3.17 INSTALLATION OF BENCHES**

- A. Install benches in accordance with manufacturer's instructions at locations indicated on the Drawings.
- B. Install benches level.
- C. Anchor benches securely in place.
- D. Finish Damage: Repair minor damages to finish in accordance with manufacturer's instructions.
- E. Component Damage: Remove and replace damaged components that cannot be successfully repaired as determined by Resident Engineer.
- F. Clean benches promptly after installation in accordance with manufacturer's instructions.
- G. Do not use harsh cleaning materials or methods that could damage finish.
- H. Protect installed benches to ensure that, except for normal weathering, benches will be without damage or deterioration at time of Substantial Completion.

- - - E N D - - -