

GENERAL NOTES:

- A. SUSPENDED ACOUSTICAL CEILINGS SHALL BE 8'-0" ABOVE FINISH FLOOR UNLESS NOTED OTHERWISE.
- B. LIGHT FIXTURES, GRILLES, DIFFUSERS, ETC. ARE SHOWN FOR GENERAL LOCATIONS ONLY. COORDINATE WITH THE MECHANICAL AND ELECTRICAL DRAWINGS.
- C. CEILING MOUNTED EQUIPMENT SHALL BE LOCATED SQUARE AND SYMMETRICAL TO ADJACENT COMPONENTS OR CONSTRUCTION UNLESS NOTED OTHERWISE.
- D. REFER TO FINISH SCHEDULE FOR GYPSUM BOARD SURFACES.
- E. WHERE ACOUSTICAL CEILINGS OCCUR, FIRE SPRINKLER HEADS SHALL BE CENTERED IN THE TILE UNLESS OTHERWISE INSTRUCTED BY CODE.
- F. THE CEILING SPACE FROM THE BOTTOM OF THE CEILING GRID TO A MINIMUM OF 6" ABOVE THE BOTTOM OF THE CEILING GRID IS RESERVED FOR INSTALLATION OF CEILING MOUNTED ITEMS (I.E. LIGHT FIXTURES, SPEAKERS, DIFFUSERS). NO PIPING, DUCTWORK, CONDUIT, ETC., EXCEPT DROPS SERVING THE CEILING MOUNTED ITEMS, IS ALLOWED TO BE INSTALLED IN THE SPACE, UNLESS OTHERWISE APPROVED BY THE COTR.
- G. THE DRAWINGS INDICATE LOCATION, DIMENSIONS, REFERENCE, AND TYPICAL DETAILS OF CONSTRUCTION. THE DRAWINGS DO NOT INDICATE EVERY CONDITION -- WORK NOT PARTICULARLY DETAILED SHALL BE OF CONSTRUCTION TO PARTS THAT ARE DETAILED. THESE DRAWINGS HAVE BEEN DEVELOPED FROM RECORDS FURNISHED BY THE OWNER AND FIELD SURVEYS. MATERIALS, DIMENSIONS, WALL THICKNESS, ROUGH OPENINGS, PATTERNS, AND THE LIKE ARE INTERPRETATIONS OF THOSE RECORDS AND SHALL BE FIELD VERIFIED BY THE CONTRACTOR. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO COMMENCING WITH THE WORK.
- H. PROTECT EXISTING WORK TO REMAIN FROM DAMAGE DURING CONSTRUCTION. ANY MATERIALS, SYSTEMS, COMPONENTS, FINISHES, AND THE LIKE, DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED TO OWNER'S ACCEPTANCE AT CONTRACTOR'S EXPENSE.
- I. MECHANICAL, PLUMBING, FIRE PROTECTION AND ELECTRICAL DUCTS, PIPES AND CONDUITS SHALL BE COMPLETELY CONCEALED IN WALLS, CEILINGS, AND FLOORS, U.O.N. TRENCH EXISTING WALLS, CEILINGS AND FLOORS AS REQUIRED TO CONCEAL DUCTS, PIPES AND CONDUITS.


SHEET NOTES:

1. REMOVE LOOSE PAINT FROM EXISTING PORCH CEILING, PATCH, REPAIR, SAND SMOOTH, PRIME, AND PAINT.
2. REMOVE (E) CEILING PANELS FROM PORCH STRUCTURE AND REPLACE WITH HARDI BOARD BEADED PORCH PANEL.
3. PATCH AND REPAIR ANY AREAS WHERE GYPSUM BOARD CEILING PANELS ARE BROKEN OR MISSING. PATCH, REPAIR, AND SEAL AROUND ANY CEILING OR WALL PENETRATIONS THROUGH GYPSUM BOARD OR MASONRY.
4. PAINTED WOOD CORNICE.

LEGEND:

- MECHANICAL EXHAUST HOOD
- MECHANICAL RETURN GRILLE
- MECHANICAL RETURN GRILLE
- MECHANICAL SUPPLY GRILLE
- MECHANICAL SUPPLY GRILLE
- LIGHT FIXTURE, RECESSED FLUORESCENT
- LIGHT FIXTURE, RECESSED FLUORESCENT
- LIGHT FIXTURE, INDIRECT PENDANT FLUORESCENT
- LIGHT FIXTURE, SURFACE MOUNTED FLUORESCENT
- LIGHT FIXTURE, WALL MOUNTED
- LIGHT FIXTURE, RECESSED CAN LIGHT
- LIGHT FIXTURE, FLUORESCENT EMERGENCY AND NIGHT LIGHT
- LIGHT FIXTURE, FLUORESCENT EMERGENCY AND NIGHT LIGHT
- LIGHT FIXTURE, FLUORESCENT EMERGENCY AND NIGHT LIGHT
- WALL MOUNT EMERGENCY EXIT SIGN
- EMERGENCY EXIT SIGN
- MOTION DETECTOR
- 2x4 SUSPENDED CEILING GRID
- 2x4 SUSPENDED CEILING GRID WITH 2x2 SCORED ACOUSTICAL PANELS
- SUSPENDED GYPSUM BOARD CEILING
- 8'-0" CEILING HEIGHT
- VIDEO CONFERENCE PROJECTOR OR CAMERA
- IP FIXED CCTV CAMERA
- LOCAL ALARM INDICATOR


1 GROUND FLOOR REFLECTED CEILING PLAN BLDG. 33



SCALE: 1/8" = 1'-0"



2 FIRST FLOOR REFLECTED CEILING PLAN BLDG. 33



SCALE: 1/8" = 1'-0"



95% SUBMISSION

REVISIONS DATE

CSHQ

C.W. MOORE PLAZA
250 S. 5TH ST. • BOISE, ID 83702
(208) 343-4635 • FAX (208) 343-1858
http://www.cshqa.com

JOHN D. MAULIN, ARCHITECT
C.W. MOORE PLAZA
250 S. 5TH ST.
BOISE, IDAHO
PHONE: 208-343-4635 FAX: 208-343-1858

THESE DRAWINGS AND SPECIFICATIONS, AS INSTRUMENTS OF SERVICE, ARE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT / ENGINEER. NO PART OF THESE DRAWINGS OR SPECIFICATIONS SHALL BE USED BY ANY PERSON OR ENTITY, IN ANY PROJECT, FOR ANY PURPOSE, WITHOUT THE WRITTEN CONSENT OF CSHQA OR ITS AFFILIATES. Copyright © 2011

STAMP

PRELIMINARY
NOT FOR
CONSTRUCTION

DRAWING TITLE

REFLECTED CEILING PLANS

APPROVED: DIVISION CHIEF

APPROVED: SERVICE DIRECTOR

PROJECT TITLE

VAMC
RENOVATE
BUILDING 33

BUILDING NUMBER

33

LOCATION

BOISE, IDAHO

CHECKED

JMO

DRAWN

BKS

DATE

03/04/11

PROJECT NO.

531-10-114

DRAWING NO.

A9.1

DWG. 43 OF 102

DEPARTMENT OF VETERANS AFFAIRS