

5 EGRESS EXTERIOR LIGHTING BATTERY BACKUP DIAGRAM

SCALE: NONE



4 EMERGENCY INTERIOR LIGHTING BATTERY BACKUP DIAGRAM

SCALE: NONE

ID: LCP
Location: Storage Room 113
Supply Circuit: 1-16 Voltage: 120

Relay	Line Feed	Type	Voltage	Source	Description	Relay	Line Feed	Type	Voltage	Source	Description
1	1-4	NC	120V	Normal	Reception 106	2	1-4	NC	120V	Normal	Waiting 104
3	1-4	NC	120V	Normal	Reception Downlights 106	4	1-9	NC	120V	Normal	Corridors C12,C13,C14
5	1-5	NC	120V	Normal	Lobby 101	6	1-5	NC	120V	Normal	Stairs ST12
7	1-7	NC	120V	Normal	Lobby Emergency 101, Stairs ST12	8	1-10	NC	120V	Normal	Exterior Building Lights
9	1-12	NC	120V	Normal	Exterior Emergency Building Lights	10	2-4	NC	120V	Normal	Reception 206
11	2-4	NC	120V	Normal	Waiting 204	12	2-4	NC	120V	Normal	Reception Downlights 206
13	2-5	NC	120V	Normal	Corridors C21,C22,C23,C24	14	3-2	NC	120V	Normal	Corridors C31
15	1-14	NC	120V	Normal	Exterior Ground Lights	16	-	NC	120V	Normal	Spare

Part #: LIGHTING CONTROL SYSTEM MANUFACTURER LIGHTING CONTROL & DESIGN: GR1416LT/16 DTC-HL-SM OR EQUAL
Enclosure Dimensions: 17.1"[434mm]H x 10.6"[269mm]W x 2.9"[74mm]D
NEMA Rating: 1

1 PANEL RELAY SCHEDULE - LCP

SCALE: NONE



3 LIGHTING CONTROLS - LOW VOLTAGE SINGLE LINE DIAGRAM

SCALE: NONE

ID: LV1
Part #: CH-4-IV-ST

Location: Waiting 104

Button	Name	Function	Relay Controlled	Color	ENGRAVING Line 1	ENGRAVING Line 2
1	BUTTON 1	Toggle	LCP-1	Ivory	WAITING	On/Off
2	BUTTON 2	Toggle	LCP-2	Ivory	RECEPT DESK	On/Off
3	BUTTON 3	Toggle	LCP-3	Ivory	DOWNLIGHTS	On/Off
4	BUTTON 4	Toggle	LCP-1,2,3	Ivory	ALL OFF	

SWITCH SCHEDULE - LV1

ID: LV2-A, LV2-B, LV2-C
Part #: CH-1-IV-ST

Location: Corridor C12, C13, C14

Button	Name	Function	Relay Controlled	Color	ENGRAVING Line 1	ENGRAVING Line 2
1	BUTTON 1	Toggle	LCP-4	Ivory	CORRIDORS	On/Off

• CONTROLS NORMAL AND EMERGENCY LIGHT FIXTURES.

SWITCH SCHEDULE - LV2-A, LV2-B, LV2-C

ID: LV3-A, LV3-B, LV3-C
Part #: CH-4-IV-ST

Location: STAIRS ST12, ST22, ST32

Button	Name	Function	Relay Controlled	Color	ENGRAVING Line 1	ENGRAVING Line 2
1	BUTTON 1	Toggle	LCP-5	Ivory	LOBBY	On/Off
2	BUTTON 2	Toggle	LCP-6	Ivory	SCONCES	On/Off
3	BUTTON 3	Toggle	LCP-7	Ivory	STAIRS	On/Off
4	BUTTON 4	Toggle	LCP-5,6,7	Ivory	ALL OFF	

• CONTROLS NORMAL AND EMERGENCY LIGHT FIXTURES.

SWITCH SCHEDULE - LV3-A, LV3-B, LV3-C

ID: LV4
Part #: CH-4-IV-ST

Location: Reception 204

Button	Name	Function	Relay Controlled	Color	ENGRAVING Line 1	ENGRAVING Line 2
1	BUTTON 1	Toggle	LCP-10	Ivory	WAITING	On/Off
2	BUTTON 2	Toggle	LCP-11	Ivory	RECEPT DESK	On/Off
3	BUTTON 3	Toggle	LCP-12	Ivory	DOWNLIGHTS	On/Off
4	BUTTON 4	Toggle	LCP-10,11,12	Ivory	ALL OFF	

SWITCH SCHEDULE - LV4

ID: LV5-A, LV5-B, LV5-C
Part #: CH-1-IV-ST

Location: Corridor C21,C22,C23

Button	Name	Function	Relay Controlled	Color	ENGRAVING Line 1	ENGRAVING Line 2
1	BUTTON 1	Toggle	LCP-13	Ivory	CORRIDORS	On/Off

• CONTROLS NORMAL AND EMERGENCY LIGHT FIXTURES.

SWITCH SCHEDULE - LV5-A, LV5-B, LV5-C

ID: LV6-A, LV6-B
Part #: CH-1-IV-ST

Location: Corridor C31

Button	Name	Function	Relay Controlled	Color	ENGRAVING Line 1	ENGRAVING Line 2
1	BUTTON 1	Toggle	LCP-14	Ivory	CORRIDOR	On/Off

• CONTROLS NORMAL AND EMERGENCY LIGHT FIXTURES.

SWITCH SCHEDULE - LV6

2 SWITCH SCHEDULES

SCALE: NONE

LIGHTING CONTROL SYSTEM SPECIFICATION:

1. LIGHTING CONTROL SYSTEM SHALL BE DIGITAL AND CONSIST OF A MASTER LCP WITH UP TO 16 INDIVIDUAL RELAYS. ANALOG SYSTEMS ARE NOT ACCEPTABLE. ALL CABLES SUPPLIED BY CONTRACTOR.
2. RELAY PANELS SHALL BE PRE-WIRED, PRE-ASSEMBLED, PREPROGRAMMED AND LISTED TO UL 916 (NORMAL). PANELS SHALL BE PROVIDED WITH DUAL VOLTAGE POWER SUPPLY.
3. RELAYS SHALL BE ZERO-CROSS TYPE. NO EXCEPTIONS. RATED FOR 120/277V 20A TUNGSTEN, BALLAST OR HID. STANDARD STANDARD RELAYS SHALL HAVE NORMALLY CLOSED (NC) CONTACTS
4. RELAY PANEL ELECTRONICS SHALL PROVIDE CURRENT VISUAL STATUS AND CONTROL OF EACH RELAY OR ZONE. ALL SYSTEM CONTROL ELECTRONICS SHALL STORE PROGRAMMING IN A NON-VOLATILE MEMORY AND PROVIDE 10 YEAR BATTERY BACK UP FOR TIME OF DAY.
5. LIGHTING CONTROL SYSTEM SHALL CONSIST OF MASTER PANEL CONTROLLED BY A 32-CHANNEL DIGITAL TIME CLOCK (DTC) THAT CONTROLS AND PROGRAMS THE ENTIRE LIGHTING CONTROL SYSTEM. THE DTC SHALL SUPPLY ALL TIME FUNCTIONS AND ACCEPT OTHER INPUTS. THE DTC SHALL ACCEPT CONTROL LOCALLY USING BUILT IN BUTTON PROMPTS AND USE OF AN 8 LINE 21-LETTER DISPLAY, FROM A COMPUTER, MODEM, ETHERNET OR INTERNET. ALL COMMANDS SHALL BE IN PLAIN ENGLISH. HELP PAGES SHALL DISPLAY ON THE DTC SCREEN.
6. ALL SWITCHES SHALL COMMUNICATE VIA RS 485, CAT 5 PATCH CABLE WITH RJ45 CONNECTORS. CONTACT CLOSURE STYLE SWITCHES ARE NOT ACCEPTABLE. ANY SWITCH BUTTON FUNCTION SHALL BE ABLE TO BE CHANGED LOCALLY (AT THE DTC OR A PC) OR REMOTELY, VIA MODEM, ETHERNET OR INTERNET. REFER TO LIGHTING CONTROLS LOW VOLTAGE SINGLE LINE DIAGRAM FOR WIRING DETAILS. SWITCHES WHICH CANNOT BE PROGRAMMED REMOTELY SHALL NOT BE ACCEPTABLE.
7. LIGHTING CONTROL SYSTEM INTERFACES TO INCLUDE A DRY CONTACT INPUT INTERFACE, BMS INTERFACE, AND ETHERNET/INTERNET INTERFACE. VERIFY AND INSTALL ONLY THOSE INTERFACES INDICATED ON THE PLANS.
8. STANDARD LIGHTING CONTROL SYSTEM SOFTWARE, PRE-INSTALLED INTO THE DTC, SHALL CONSIST OF AND USE STANDARD GRAPHICAL MANAGEMENT SOFTWARE (GMS) PAGES. GMS SOFTWARE SHALL PROVIDE VIA LOCAL OR REMOTE PC A VISUAL REPRESENTATION OF EACH DEVICE ON THE BUS, SHOW REAL TIME STATUS AND THE ABILITY TO CHANGE THE STATUS OF ANY INDIVIDUAL DEVICE, RELAY OR ZONE. OPTIONAL SOFTWARE THAT ACCEPTS JOB SPECIFIC GRAPHICS SHALL BE AVAILABLE. NO EXCEPTIONS.
9. START UP: ELECTRICAL CONTRACTOR SHALL CONTACT EQUIPMENT MANUFACTURER AT LEAST 7 DAYS BEFORE TURNOVER OF PROJECT. EQUIPMENT MANUFACTURER SHALL REMOTELY DIAL INTO THE LIGHTING CONTROL SYSTEM, RUN DIAGNOSTICS AND CONFIRM SYSTEM PROGRAMMING. ELECTRICAL CONTRACTOR SHALL BE AVAILABLE AT THE TIME OF DIAL IN TO PERFORM ANY CORRECTIONS REQUIRED. ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH GENERAL CONTRACTOR AND THE OWNER, THE INSTALLATION OF A DEDICATED TELEPHONE LINE OR A SHARED PHONE LINE WITH A/B SWITCH. PHONE JACK TO BE MOUNTED WITHIN 12" OF MASTER LCP. LABEL JACK WITH PHONE NUMBER. ELECTRICAL CONTRACTOR SHALL CONNECT PHONE LINE FROM JACK TO MASTER LCP. NO EXCEPTIONS.
10. TELEPHONE FACTORY DIAL-UP SUPPORT SHALL BE AVAILABLE AT NO ADDITIONAL COST TO THE ELECTRICAL CONTRACTOR OR OWNER BOTH DURING AND AFTER THE 3 YEAR WARRANTY PERIOD. FACTORY TO PREPROGRAM THE LIGHTING CONTROL SYSTEM PER PLANS AND APPROVED SUBMITTAL. THE LIGHTING CONTROL MANUFACTURER, AT NO ADDED COST, SHALL PROVIDE ADDITIONAL PROGRAMMING VIA MODEM AS REQUIRED BY THE ELECTRICAL CONTRACTOR OR OWNER FOR THE OPERATIONAL LIFE OF THE SYSTEM. MANUFACTURER WARRANTS THAT THE DTC SOFTWARE CAN BE UPGRADED AND MONITORED REMOTELY. NO EXCEPTIONS.
11. SHOP DRAWINGS: SUBMIT DIMENSIONED DRAWINGS OF LIGHTING CONTROL SYSTEM AND ACCESSORIES INCLUDING, BUT NOT NECESSARILY LIMITED TO, RELAY PANELS, SWITCHES, DTC, PHOTOCELLS AND OTHER INTERFACES. DRAWINGS SHALL INDICATE EXACT LOCATION AND PROGRAMMING OF EACH DEVICE. INDICATE ALL TIME SCHEDULES AND SWITCH BUTTON ENGRAVING.
12. LIGHTING CONTROL SYSTEM SPECIFIED IS BASED ON LIGHTING CONTROL & DESIGN (LC&D), LOS ANGELES, CA (800) 345-4448. LIGHTING CONTROL SYSTEM SHALL MEET OR EXCEED LC&D SYSTEM SPECIFIED.

95% SUBMISSION

REVISIONS	DATE

CSHQA

C.W. MOORE PLAZA
250 S. 5TH ST. • BOISE, ID 83702
(208) 343-4635 • FAX (208) 343-1858
http://www.cshqa.com

AMY K. DOCKTER, P.E.
C.W. MOORE PLAZA
250 S. 5TH ST
BOISE, IDAHO
PHONE: 208-343-4635 FAX: 208-343-1858

THESE DRAWINGS AND SPECIFICATIONS, AS INSTRUMENTS OF SERVICE, ARE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT / ENGINEER WHETHER THE PROJECT FOR WHICH THEY ARE MADE IS EXECUTED OR NOT. THESE DRAWINGS AND SPECIFICATIONS SHALL NOT BE USED BY ANY PERSON OR ENTITY ON OTHER PROJECTS, FOR ADDITIONS TO THIS PROJECT OR FOR COMPLETION OF THIS PROJECT BY OTHERS WITHOUT THE WRITTEN CONSENT OF CSHQA OR ITS AFFILIATES. Copyright ©2011

STAMP

PRELIMINARY
NOT FOR
CONSTRUCTION

DRAWING TITLE: LIGHTING CONTROLS

PROJECT TITLE: VAMC RENOVATE BUILDING 33

APPROVED: DIVISION CHIEF

APPROVED: SERVICE DIRECTOR

BUILDING NUMBER: 33 | CHECKED: AKD | DRAWN: CRP

LOCATION: BOISE, IDAHO

DATE: 03/04/11

PROJECT NO.: 531-10-114

DRAWING NO.: E0.3

DWG. 80 OF 102

DEPARTMENT OF VETERANS AFFAIRS

Username: dpjo
Mar 08, 2011 - 10:52am
O:\2009\09004.6\Phase 2 - Renovations\Elec\02_Drawings\E03.dwg