







GENERAL NOTES:

- A. MAKE ALL CONNECTIONS TO EQUIPMENT PER MANUFACTURER'S REQUIREMENTS. B. ROUTE ALL CONDUIT HOME RUNS TO PANELS OVERHEAD AND ABOVE ACCESSIBLE CEILINGS WHERE AVAILABLE.
- C. PROVIDE POWER RELAYS, LOW VOLTAGE TRANSFORMERS, SECURITY CONDUITS AND JUNCTION BOXES AS REQUIRED FOR SECURITY SYSTEM CONNECTIONS. SECURITY SYSTEM CABLING AND EQUIPMENT BY OTHERS. COORDINATE ELECTRICAL REQUIREMENTS FOR A COMPLETE AND OPERATIONAL SYSTEM WITH ARCHITECTURAL DOOR HARDWARE SCHEDULE, ARCHITECT, SECURITY SYSTEM PROVIDER AND OWNERS AGENT. VERIFY ALL REQUIREMENTS PRIOR TO
- D. ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE TO REVIEW MECHANICAL DRAWINGS AND SUBMITTALS, AND PROVIDE ALL LINE VOLTAGE POWER AND INTERLOCK CONDUIT, CONDUCTORS AND TERMINATIONS FOR FULLY OPERATIONAL SYSTEMS. CONDUIT FOR CONTROL WIRING SHALL BE BY ELECTRICAL CONTRACTOR. CONTROL WIRING AND CONNECTIONS FOR MECHANICAL EQUIPMENT SHALL BE BY CONTROLS CONTRACTOR.
- E. COORDINATE ALL CONTROL WORK WITH THE MECHANICAL CONTRACTOR. FURNISH AND INSTALL ALL ELECTRICAL BOXES AND CONDUIT RUNS REQUIRED PER MECHANICAL DRAWINGS.
- F. FURNISH AND INSTALL MOTOR STARTERS, DISCONNECTS AND FUSES AS REQUIRED BY EQUIPMENT RATINGS AND MANUFACTURERS RECOMMENDATIONS.
- G. COORDINATE MOUNTING HEIGHTS AND ORIENTATION OF DEVICES IN MILLWORK WITH ARCHITECTURAL ELEVATIONS.

SHEET NOTES:

- . SURFACE MOUNTED LIGHT FIXTURE MOUNTED TO BOTTOM OF LANDING. CONCEAL CONDUIT. MAKE CONNECTIONS AS INDICATED.
- 2. WALL MOUNT BOTTOM OF SCONCE LIGHT FIXTURE AT 7'-0" [2134mm] ABOVE FINISHED FLOOR OR LANDING. CONCEAL CONDUIT IN WALLS. MAKE CONNECTIONS AS INDICATED.
- FLOOR OR LANDING. CONCEAL CONDUIT IN WALLS. MAKE CONNECTIONS AS 4. WALL MOUNT BOTTOM OF LIGHT FIXTURE AT 7'-6" [2286mm] ABOVE FINISHED

3. WALL MOUNT BOTTOM OF LIGHT FIXTURE AT 9'-6" [2896mm] ABOVE FINISHED

- FLOOR OR LANDING. CONCEAL CONDUIT IN WALLS. MAKE CONNECTIONS AS
- 5. SURFACE MOUNTED MOTION SENSOR/PHOTOCELL. CONCEAL CONDUIT. MAKE CONNECTIONS AS INDICATED.
- 6. FOR CONTINUATION OF CIRCUIT IN STAIRWELL SEE SHEET E2.5.
- 7. SURFACE MOUNTED LIGHT FIXTURE MOUNTED TO BOTTOM OF STRUCTURE.

CONCEAL CONDUIT. MAKE CONNECTIONS AS INDICATED.

95% SUBMISSION

C.W. MOORE PLAZA 250 S. 5TH ST. • BOISE, ID 83702 (208) 343-4635 • FAX (208) 343-1858 http://www.cshqa.com



AMY K. DOCKTER, P.E.



STAIR	DETAILS	
APPROVED:	DIVISION CHIEF	

APPROVED: SERVICE DIRECTOR

DRAWING TITLE

TAILS	PROJECT TITLE VAMC RENOVATE BUILDING 33			DATE 03/04/1 PROJECT NO. 531-10-
CHIEF	BUILDING NUMBER 33	CHECKED AKD	DRAWN CRP	DRAWING NO.

BOISE, IDAHO

